

BID PROPOSAL FOR
 PAID CAMPUS IMPROVEMENTS
 THE WOODLANDS TOWNSHIP

CONTRACTOR: _____

DATE: _____

Date valued the and signature: _____

I hereby acknowledge receiving the following addendums as applicable:

Addendum No. 1 Sign: _____
 Addendum No. 2 Sign: _____
 Addendum No. 3 Sign: _____

Date: _____
 Date: _____
 Date: _____

ITEM NO.	Spec	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENDED TOTAL
SERIES 100: GENERAL						
100	1100	ADJUSTMENT	1	LS		\$ -
101		ADJUST	1	LS		\$ -
SERIES 100 TOTAL						\$ -

SERIES 200: STORM WATER POLLUTION PREVENTION PLAN						
200	CDH 011570	SWPPP INSPECTION AND MAINTENANCE (MAX 800 - 52,000/ANNU)	8	MS		\$ -
201	CDH 011575	CONCRETE TRUCK WASHOUT STRUCTURES (80% OF UNIT COST FOR FURNISH AND INSTALLATION, AND 20% ROLL-COST FOR REMOVAL)	1	BA		\$ -
202	CDH 011570	PALET PROTECTION BARRIER (STAGE 2, WITH FIBER ROLLS, 60% OF UNIT COST FOR FURNISH AND INSTALLATION, AND 40% OF UNIT COST FOR REMOVAL)	2	BA		\$ -
203	CDH 011570	PALET PROTECTION BARRIER (STAGE 2, WITH FIBER ROLLS, 60% OF UNIT COST FOR FURNISH AND INSTALLATION, AND 40% OF UNIT COST FOR REMOVAL)	14	BA		\$ -
204	CDH 011575	STABILIZED CONSTRUCTION ACCESS (TYPE 1 ROCK, 60% OF UNIT COST FOR FURNISH AND INSTALLATION, AND 40% OF UNIT COST FOR REMOVAL)	108	SY		\$ -
205	CDH 011570	REINFORCED FILTER FABRIC FENCE (80% OF UNIT COST FOR FURNISH AND INSTALLATION AND 20% OF UNIT COST FOR REMOVAL)	624	LF		\$ -
206	CDH 011570	PROCES GENERAL PERMIT NO. TWO (100% NOTICE OF INTENT (NOI) APPLICATION FEE (CONTRACTOR'S NO. FEE SHALL BE FIXED PRICE OF \$225.00)	1	BA		\$ -
SERIES 200 TOTAL						\$ -

SERIES 300: SITE PREPARATION AND EARTHWORK						
300	CDH 022225	SITE PREPARATION INCLUDING BUT NOT LIMITED TO CLEARING OF TURF, LANDSCAPING, AND OTHER IMPROVEMENTS WITHIN THE WORK AREA	1.40	AC		\$ -
301	CDH 022232	FILL IMPORT (IMPORTED MATERIAL, INCLUDING HAULING AND COMPACTION)	2240	CY		\$ -
302	CDH 022139	SELECTED BORROW FOR BUILDING AND IMPORTED SOILS	434	CY		\$ -
303	CDH 022233	CLEARING AND GRUBBING OF EXISTING TREES, ALL SIZES, INCLUDING CHIPPING AND OFF-SITE DISPOSAL, AS SHOWN OR APPROVED PLANS AND COORDINATED WITH OWNER	0.04	AC		\$ -
SERIES 300 TOTAL						\$ -

SERIES 400: DEMOLITION PHASE 2						
400	CDH 02221	REMOVE AND DISPOSE CONCRETE PAVEMENT (ALL DEPTHS, INCLUDING SIDEWALKS) INCLUDING SUB-BASE AND SUBGRADE	649	SY		\$ -
401	CDH 02221	REMOVE AND DISPOSE ASPHALT PAVEMENT (ALL DEPTHS) INCLUDING SUB-BASE, SUBGRADE, AND CURB	5,460	SY		\$ -
402	CDH 02229	REMOVE AND DISPOSE GRAVEL (ALL DEPTHS) INCLUDING SUB-BASE, SUBGRADE, AND CURB	1,949	SY		\$ -
403	CDH 02223	REMOVE AND DISPOSE BRICK PAVEMENT	86	SY		\$ -
404	CDH 02222	REMOVE AND DISPOSE DECOMPOSED GRANITE (ALL DEPTHS) INCLUDING SUB-BASE	78	SY		\$ -
405	CDH 02221	REMOVE EXISTING 12" DRAIN, STRIP AND REMOVE ALL SOFT AND WET SOILS (DE-MULCHING SHALL EXTEND TO THE DEPTH OF THE COMPETENT MATERIAL PER GEOTECH REPORT)	122	LF		\$ -
406	CDH 02221	DE-MULCH EXISTING POND, DRAIN, STRIP AND REMOVE ALL SOFT AND WET SOILS (DE-MULCHING SHALL EXTEND TO THE DEPTHS OF THE COMPETENT MATERIAL PER GEOTECH REPORT)	1	LS		\$ -
407	CDH 02762	REMOVE PAVEMENT MARKINGS	2042	LF		\$ -
408	CDH 02221	REMOVE AND DISPOSE EXISTING CONCRETE CURB	148	LF		\$ -
409	CDH 02221	REMOVE AND DISPOSE EXISTING RAILINGS	1	BA		\$ -
410	CDH 02221	REMOVE AND DISPOSE EXISTING 4" PVC PIPE	3	LF		\$ -
411	CDH 02221	REMOVE AND DISPOSE EXISTING 12" COP STORM PIPE	220	LF		\$ -
412	CDH 02221	REMOVE AND DISPOSE EXISTING 12" COP STORM PIPE	99	LF		\$ -
413	CDH 02221	REMOVE AND DISPOSE EXISTING 18" COP STORM PIPE	17	LF		\$ -
414	CDH 02221	REMOVE AND DISPOSE 4" BRASS INLET	1	BA		\$ -
415	CDH 02221	REMOVE AND DISPOSE PLASTIC READING SIGN	4	BA		\$ -
416	CDH 02221	REMOVE AND DISPOSE EXISTING 4" WOODEN FENCE	36	LF		\$ -
417	CDH 02221	REMOVE AND DISPOSE EXISTING 12" COP STORM PIPE	296	LF		\$ -
418	CDH 02221	REMOVE AND DISPOSE STEEL CABLE WITH WOODEN POSTS	38	LF		\$ -
419	CDH 02221	REMOVE AND DISPOSE EXISTING METAL SLING GATE AND POSTS	1	LS		\$ -
420	CDH 02211	REMOVE AND RETURN EXISTING MAIN WATER COLLECTION TRUNK AND SYSTEM TO THE WOODLANDS TOWNSHIP	1	LS		\$ -
421	CDH 02221	REMOVE AND DISPOSE EXISTING IRRIGATION SYSTEM	1	LS		\$ -
422	CDH 02221	REMOVE AND DISPOSE EXISTING ELECTRICAL BOX	1	BA		\$ -
423	CDH 02221	REMOVE AND REPLACE STEEL FRAMING	1	BA		\$ -
424	CDH 02221	REMOVE AND REPLACE STEEL REINFORCEMENT	1	BA		\$ -
425	CDH 02221	REMOVE AND RELOCATE EXISTING TRUCK SIGN	2	BA		\$ -
426	CDH 02221	REMOVE AND RETURN EXISTING SITE FURNISHINGS INCLUDING STAIRS, WALKING BRIDGE, GATES AND POSTS, RETING, BOLLARDS, BINE RAIL, SECURITY CAMERA, WOOD POST, HANDING SIGN AND TRUNK LANE TO THE WOODLANDS TOWNSHIP	1	LS		\$ -
427	CDH 02211	REMOVE AND RETURN EXISTING LIGHT POLE, AC UNITS AND MISC. ELECTRICAL ITEMS TO THE WOODLANDS TOWNSHIP	1	LS		\$ -
428	CDH 02221	REMOVE AND DISPOSE OF EXISTING LIGHT POLE CONCRETE FOUNDATIONS	2	BA		\$ -
SERIES 400 TOTAL						\$ -

SERIES 500: UTILITIES						
500	CDH 02611	18" MCP STORM SEWER (ALL DEPTHS) COMPLETE IN PLACE	187	LF		\$ -
501	CDH 02611	18" MCP STORM SEWER (ALL DEPTHS) COMPLETE IN PLACE	138	LF		\$ -
502	CDH 02611	8" HDPE STORM SEWER (ALL DEPTHS) COMPLETE IN PLACE	73	LF		\$ -
503	CDH 02611	12" PVC TRAILER COMPLETE IN PLACE	7	BA		\$ -
504	CDH 02611	12" PVC TRAILER COMPLETE IN PLACE	8	BA		\$ -
505	CDH 02611	12" PVC TRAILER COMPLETE IN PLACE	10	BA		\$ -
506	CDH 02611	12" PVC TRAILER COMPLETE IN PLACE	227	LF		\$ -
507	CDH 02611	12" PVC TRAILER COMPLETE IN PLACE	495	LF		\$ -
SERIES 500 TOTAL						\$ -

SERIES 600: PAVING						
600	CDH 02775	4" REINFORCED CONCRETE SIDEWALK WITH 2" SAND BASE, COMPLETE IN PLACE	313	SY		\$ -
601	CDH 02741	2" ASPHALT PAVEMENT WITH 8" BASE MATERIAL AND 4" REINFORCED SUBGRADE, COMPLETE IN PLACE	1	TON		\$ -
602	CDH 02751	4" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	1,832	SY		\$ -
603	CDH 02751	4" REINFORCED CONCRETE PAVEMENT, COMPLETE IN PLACE	2,322	SY		\$ -
604	CDH 02201	1" SUBGRADE PREPARATION, INCLUDING PROOF-ROLLING, MAKING STABILIZER OR SCARIFYING AND COMPACTING TO 95% OF AASHTO 1993	4301	SY		\$ -
605	CDH 02201	HYDRATED LIME FOR SUBGRADE STABILIZATION (25 LB/TY @ 9% BY DRY UNIT WEIGHT), REFERENCE GEOTECHNICAL STUDY BY STRIMMON, PROJECT NO. 17-240057	36	TON		\$ -
606	CDH 02237	FLY ASH FOR SUBGRADE STABILIZATION (25 LB/TY @ 9% BY DRY UNIT WEIGHT), REFERENCE GEOTECHNICAL STUDY BY STRIMMON, PROJECT NO. 17-240057	95	TON		\$ -
607	CDH 02775	4" REINFORCED CONCRETE CURB, COMPLETE IN PLACE	2,080	LF		\$ -
608	CDH 02767	4" SOLID WHITE TYPE 3 PAVEMENT MARKING, INCLUDING SURFACE PREPARATION, COMPLETE IN PLACE	2,815	LF		\$ -
609	CDH 02775	ADA CURB RAMP, COMPLETE IN PLACE	1	BA		\$ -
610	CDH 02775	CONCRETE WHEELSTOP, COMPLETE IN PLACE	43	BA		\$ -
611	CDH 02767	THERMOPLASTIC HANDICAP SYMBOL, PREPAVED PAVEMENT MARKING, INCLUDING SURFACE PREPARATION, COMPLETE IN PLACE	8	BA		\$ -
612	CDH 02767	1" PAINTED HIGHWAY REFLECTIVE WHITE PAVEMENT INCLUDING MARKING SURFACE PREPARATION, COMPLETE IN PLACE	72	LF		\$ -
613	CDH 02767	1" PAINTED HIGHWAY REFLECTIVE WHITE PAVEMENT INCLUDING MARKING SURFACE PREPARATION, COMPLETE IN PLACE	12	LF		\$ -
614	CDH 02767	4" RED PAINTED FIRE LANE STRIPING FOR MONTGOMERY COUNTY FIRE CODE, COMPLETE IN PLACE	160.3	LF		\$ -
615	DWG	4" DECOMPOSED GRANITE TRAIL INCLUDING 4" CRUSHED LIMESTONE COMPACTED BASE, COMPLETE IN PLACE	2	CY		\$ -
SERIES 600 TOTAL						\$ -

SERIES 700: LANDSCAPE AND IRRIGATION						
700	129400	CHICKEN DITCH/SLUR / BERRADA GRASS SOD	12,333	SY		\$ -
701	129400	TEMPORARY IRRIGATION SYSTEM, COMPLETE IN PLACE	12,333	SY		\$ -
702	DWG	10" BLACK VINYL COATED CHAIN LINK FENCE, COMPLETE IN PLACE	158	LF		\$ -
SERIES 700 TOTAL						\$ -

SERIES 800: ARCHITECTURAL, MEP, & STRUCTURAL						
800		RENOVATION OF BUILDINGS A & B AND CONSTRUCTION OF BUILDING C	1	LS		\$ -
801		PAVING LOT LIGHTING, INCLUDING INSTALLATION OF 3-AI-VALED LIGHT POLES AND FIXTURES AND INSTALLATION OF 3 NEW LIGHT POLE FOUNDATIONS, 1 LIGHT POLE, 1 EQUIP. CONSULT AND WIRING	1	LS		\$ -
802		BUILDING HVAC COMPLETE, INSTALLED AND OPERATIONAL PER PLANS AND SPECIFICATIONS INCLUDING BUT NOT LIMITED TO EQUIPMENT, INSTALLATION, START-UP, AIR-BALANCE, CLEANUP, O&M TRAINING, LUMP SUM	1	LS		\$ -
803		BUILDING PLUMBING SYSTEM COMPLETE PER PLANS AND SPECIFICATIONS, INSTALLED AND OPERATIONAL INCLUDING BUT NOT LIMITED TO FIXTURES, EQUIPMENT AND PIPING, START-UP, TESTING, O&M TRAINING AND CLEANUP, LUMP SUM	1	LS		\$ -
804		SITE ELECTRICAL PER PLANS AND SPECIFICATIONS INCLUDING MODIFICATIONS TO SERVICE AND EXISTING DISTRIBUTION, LUMP SUM	1	LS		\$ -
805		BUILDING ELECTRICAL PER PLANS AND SPECIFICATIONS INCLUDING BUT NOT LIMITED TO LIGHTING, CONDUCTORS, CONDUIT, PANELS, BRANCH CIRCUIT BREAKERS, BRANCH CIRCUIT WIRE, ELECTRIC AND OTHER CONTROLS, RECEPTACLES, BOXES, WIRING DEVICES, SECURITY, SCADA, AND ACCESS WIRING FOR COMPLETE BUILDING ELECTRICAL SYSTEM	1	LS		\$ -
806		BUILDING FOUNDATION INCLUDING BUT NOT LIMITED TO CONCRETE, REBAR, INSTALLATION AND FINISH OUT	1	LS		\$ -
807		STRUCTURAL INSULATED PANEL SYSTEM WITH BEAMS AND POSTS, INSTALLED PER PLANS AND SPECIFICATIONS, INCLUDING BUT NOT LIMITED TO MATERIAL, EQUIPMENT AND LABOR	1	LS		\$ -
808		METAL CLAD FRAMEWORK AND EQUIPMENT SYSTEM, INSTALLED AND FINISHED COMPLETE PER PLANS AND SPECIFICATIONS	1	LS		\$ -
809		DOORS, WINDOWS, STOREFRONT, HARDWARE, INSTALLED COMPLETE PER PLANS AND SPECIFICATIONS	1	LS		\$ -
810		FOLDING PARTITION, COMPLETE PER PLANS AND SPECIFICATIONS	1	LS		\$ -
811		INSULATION, MATERIAL AND LABOR, INSTALLED PER PLANS AND SPECIFICATIONS	1	LS		\$ -
812		INTERIOR WALL FINISHES, MATERIAL AND LABOR, INSTALLED PER PLANS AND SPECIFICATIONS	1	LS		\$ -
813		INTERIOR FLOOR FINISHES, MATERIAL AND LABOR, INSTALLED PER PLANS AND SPECIFICATIONS	1	LS		\$ -
814		EXTERIOR WALL FINISHES, MATERIAL AND LABOR, INSTALLED PER PLANS AND SPECIFICATIONS	1	LS		\$ -
815		ROOF SYSTEM COMPLETE, MATERIAL AND LABOR, PER PLANS AND SPECIFICATIONS	1	LS		\$ -
816		MILKURON AND CASE GOODS, MATERIAL AND LABOR, FURNISHED AND INSTALLED PER PLANS AND SPECIFICATIONS	1	LS		\$ -
817		TOILET PARTITIONS AND ACCESSORIES INCLUDING ADA ACCESSORIES, FURNISHED AND INSTALLED PER PLANS AND SPECIFICATIONS	1	LS		\$ -
818		INTERIOR SIGNAGE	1	LS		\$ -
819		EXTERIOR SIGNAGE	1	LS		\$ -
SERIES 800 TOTAL						\$ -

BID SUMMARY						
SERIES 100 - GENERAL						
SERIES 200 - STORM WATER POLLUTION PREVENTION PLAN						
SERIES 300 - SITE PREPARATION AND EARTHWORK						
SERIES 400 - DEMOLITION PHASE 2						
SERIES 500 - UTILITIES						
SERIES 600 - PAVING						
SERIES 700 - LANDSCAPING AND IRRIGATION						
SERIES 800 - ARCHITECTURAL, MEP, & STRUCTURAL						
Base Bid Subtotal						\$ -

CALENDAR DAYS NEEDED FOR SUBSTANTIAL COMPLETION
 CALENDAR DAYS NEEDED FOR FINAL COMPLETION